

SNUBBER USERS GROUP

# SNUBBER USERS GROUP 2024 SUMMER CONFERENCE & TRADE SHOW

Call To Order Gus Avila



### ADMINISTRATIVE ITEMS

- Safety Items & Logistics
- Agenda Review
  - Afternoon Closed Session at 3 pm



# ACKNOWLEDGEMENTS & RECOGNITION



# ACKNOWLEDGEMENTS &

RECOGNITION

## CURTISS -WRIGHT

JOHN KNEZEVIC

RILEY SMITH




## PRESIDENTS AWARD



# PRESIDENTS AWARD PRESENTED TO RICK PORTMANN







## Unfortunately, Rick could not be here due to a family emergency.


# WE WERE REALLY HOPING TO BE ABLE TO HAND SOMEONE A PLAQUE HONORING THEIR SERVICE TO SNUG

SO

WE DECIDED TO DO JUST THAT.

# PRESIDENTS AWARD PRESENTED TO MITCH ETTEN-BOHM









Radioactive Materials License No. PA-1682



#### COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION BUREAU OF RADIATION PROTECTION

age 1 of 3 Rages

License No. PA 1682

RADIOACTIVE MATERIALS LICENSE

Amendment No. NEW

1.	o pny confident updatified ballow. Licenside  Anvi International LLC  20B1 Soring Road, Suite 300 Oak Brook, II 60523		In response to application dated January 31, 2023, correspondence dated June 13, 2023, August 8, 2023, and October 18, 2023, and electronic correspondence dated October 31, 2022 through March 5, 2024     License No. PA – 1682		
Byproduct, source, and/or 7.     special nuclear material		Chemical and/or physical form		8. Maximum amount that licensee may possess at any one time under this licens	
A.	Any radioactive material with atomic numbers 2 through 83, inclusive	A.	Contamination in or on nuclear reactor components	A.	No single reactor component to contain more than 500 µCl of total activity
В.	Any radioactive material with atomic numbers 64 through 95, inclusive	В.	Contam nation in or on nuclear reactor components	В.	No single reactor component to contain more than 0.50 μCi of total activity
C.	Hydragen 3	c.	Contamination as radioactive waste in hydraulic fauld or incidental on reactor components	C.	No single reactor component to contain more than 4 µGi of H-3
D.	Any radioactive material with atomic numbers 2 through 83, inclusive	D.	Contamination as radioactive waste on metal, cloth, paper, plastic, or other dry materials	D.	e0 hCI
E.	Any radioactive material with atomic numbers 84 through 95, inclusive	€.	Contamination as radigactive waste on metal, cloth, paper, plastic, or other day materials	E.	o.as µCi
F.	Tachnetlum-99	F.	Anodized Aluminum Foil Plated check source	F.	0.02 μCi
G.	Technotium-93	G.	Anodized Aluminum Fail Ptated check soutce	G.	0.005 µCi
Н.	Americium-241	н.	Anodized Alûmhum Foi Plated check source	Н.	0.905 µCi
I.	Americium-241	l:	Anodized Aluminum Foi Plated check source	I.	0.001 µCi
J.	Americium-241	J.	Anodized Aluminum disk check source	J.	0.01 µCi
ĸ.	Chlorine-36	ĸ.	Anodized Aluminum disk check source	K.	0.012 µCi
	Authorized use: hrough E. Possession in reactor compo	cident nerta.	to deconfamination, repair, resting,	and n	naintenance of snubbers and/or nuclear

### Contamination Limits per Snubber



Contamination Type Fixed Contamination Loose Contamination

 $(dpm/100 cm^2)$   $(dpm/100 cm^2)$ 

per Snubber per Snubber

Beta < 250,000 < 2200

Alpha < 250 < 20

Assumes an approximate 10% detection efficiency for fixed alpha and beta contamination using a 100 cm $^2$  alpha and beta probe  $^\sim$  1/8" from the surfaced monitored.

### **Package Limits**



All packages shipped to the ASC Service Center must be sent as a Limited Quantity per DOT regulations. Packages greater than this level won't be accepted.

Shipping papers, generated for a snubber shipping package using industry accepted software, should indicate the maximum dose rate at 1 meter from the package is 0.1 mR/hr or less.

ASC may send removed snubber parts back to the client for proper disposal at the client's facility.

### **ASC Service Center**









### ASC Service Center – Equipment

- Barker Diacon 2000NM Series Snubber Test Bench
- Mobil ICAM System
- Portable Monitor Argos 3PAB
- SAM Cronos -11
- Friskers
- Dosimetry
- Calibration Sources

### Documentation

- 23 Site Specific Procedures

### **ASC Service Center**







### **Snubber Services**



ASC Certified Service Technicians Test, Inspect, Repair and Certify contaminated snubbers under our Radioactive Material License.

Servicing all types of Mechanical & Hydraulic Snubbers

Anchor Darling Anvil Basic Engineer

Bergan Patterson Boeing E-Systems

Grinnell Lisega McDowell Wellman

Paul Munroe Power Piping PSA

### **ASC Service Center**







Thank you, please stop by our Booth or see us in our Mobile Test Trailer for additional details.


We appreciate your business!

Please email all RFQ's to: <a href="mailto:gnelson@asc-es.com">gnelson@asc-es.com</a>



Meet ASIO X FLYBOTIX








### **INTEGRATED GAS DETECTION**

- Detects, locates & quantifies 4 gases: Methane, Hydrogen Sulphide, LEL Oxygen, Carbon Monoxide. This in addition to Temperature & Humidity
- Intervene swiftly to potential hazards and keep your staff safe.
- Ensure a better asset situational awareness, and a safer working environment for humans.



Resists disturbances thanks to Radar based advanced stabilization technology.

Fly stress free anywhere

Unlock more business opportunities in harsh environments.

# STABLE IN HARSH ENVIRONMENTS




## LONGEST FLIGHT TIME

Flies 20min per battery for a full inspection in a single flight.

Maximize uptime and productivity with less back and forth to change battery for maximum.

Enjoy stress free inspections while unlocking more business opportunities.





## **ASSISTS**

### **WALL LOCK**

enables locking onto a wall at a fixed distance and angle for scanning horizontally and vertically. The angle to the wall can be set to either be 0° or 180° (facing or looking away from the wall with the camera). The distance settings can either be chosen from presets or set to "Auto" which locks the current distance.

### **VELOCITY LOCK**

prevents the drone from drifting once activated, using drone sensors to measure the drone's velocity within the environment. When using Above Water mode, the downward-facing optical-flow sensor is automatically deactivated to prevent the drone from following the flow of water.

### **TUBE LOCK**

centers the drone in the middle of a tube while moving forward. This feature works in tubes of any angle, ensuring the drone always remains centered.



#### REPULSION MODE

uses IR sensors positioned around the drone for collision avoidance, maintaining a minimum distance from detected obstacles. It is used when flying in low-dust environments with large obstacles.

#### **HEIGHT LOCK**

locks the altitude or distance to the floor, the roof, or both, maintaining the same height. This is achieved using the barometer or IR sensors and functions effectively even in dusty conditions






Protects from impacts and collisions.

Fly again after impacts and collisions.

Save on repair cost thanks to top durability & survivability.



### ASIO X



### **INSPECTION WORKFLOW**



Flybotix is taking the ASIO solution from data collection, to a whole new data centric solution that will, in addition, enable data management, data processing & predictive maintenance



### ASIO X

## Streamlined inspection process Fast decision making





### Snubbers Rotated from Stock



### Snubber Replacement

ISTD-1600 currently requires the user to follow the rules of the ASME Boiler & Pressure Vessel Code, Section XI, when replacing a snubber.

### **ISTD-1600 Snubber Modification and Replacement**

Snubber repair and replacement activities shall be performed in accordance with ASME BPVC, Section XI, as applicable.

**ISTD-1610 Suitability.** Replacement or modified snubber(s) shall have a proven suitability for the application and environment.




# Paragraph IWA-4132 of ASME Section XI specifies the requirements for replacing snubbers

### IWA-4132 States:

### **IWA-4132 Items Rotated From Stock**

Snubbers, pumps, pressure relief valves, control rod drive mechanisms, or pressure-retaining items of pump seal packages, rotated from stock need not meet any other requirement of Article IWA-4000, provided the following requirements are met:




(a) The rotation shall be only for testing or preventive maintenance of the removed items.

This means that IWA-4132 requirements can only be applied if the snubber is being replaced to be tested or because of service life monitoring requirements.




(b) Items being removed and installed shall be of the same design and construction.

This means that the replacement snubber must be identical to the snubber being removed. If a design change package is required, IWA-4132 requirements cannot be used.



(c) Items being removed shall have no evidence of failure at the time of removal.

If a snubber has failed a visual examination or is being removed to be tested because its operational readiness is in question, IWA-4132 requirements cannot be used.




(d) Items being rotated shall be removed and installed only by mechanical means.

If the snubber being removed or installed is only pinned in the support, IWA-4132 can be used. If cutting, welding or grinding is required to remove or install a snubber, IWA-4132 requirements cannot be used.




(e) Items being installed shall previously have been in service.

This one is a little tricky. A brand new snubber has obviously never been in service, so IWA-4132 would not apply. However, from an ASME standpoint, a snubber that has only previously been installed in a non-ASME support has also never been in service because it has not been certified for use in an ASME application by way of being documented on an ASME Code Data Report (N-5, NIS-2, NIS-2A, etc.).




(f) The Owner shall track the items, by unique item identification, to ensure traceability of the installed location and inservice inspection and testing records.

The Owner must have records of all the places that the snubber has been since it was new so that a complete history of the locations the snubber has been installed in can be traced.



(g) Use of an Inspector and an NIS-2 form are not required.

If you have met all the requirements previously outlined, then your ASME Code Engineer does not have to complete an NIS-2 Form or notify the Authorized Nuclear Inservice Inspector (ANII) of the replacement.




(h) Repair/replacement activities on removed items shall be performed in accordance with the requirements of this Article.

If you have plans to use the removed snubber in an ASME application in the future, then a Repair Replacement Activity package must be initiated by the ASME Code Engineer to continue traceability of the removed snubber for future use.



### Snubber Replacement

If you have met ALL the requirements of the previous slides that describe IWA-4132 requirements, then your snubber can be replaced from rotated stock without completing all the ASME Code required forms and making notifications to the ASME Code Engineer or the ANII. If you have not met all the requirements outlined previously, then your ASME Code Engineer must be notified, and additional documentation will be required.



# **Questions? Comments?**



#### MORNING BEVERAGE BREAK SPONSORED BY



RETURN BY 10:00 AM

# BEYOND CODE REQUIREMENTS – BEST PRACTICES

▶ SNUG 2024

#### **PURPOSE**

The purpose of this presentation is to provide activities performed at utilities that may be considered best practices for qualification, examination, testing, and service life monitoring.

#### **VISUAL EXAMINATION**

- ► Some sites have qualified their snubber examination personnel to be able to perform the visual exams on the snubber, and the support(s), similar to what was done previously under Section XI, IWF-5000.
- ► Some sites on OMN-13 have broken up their 100% visual examinations over several outages to levelize scope, align snubber examinations with train outages, and reduce the burden of completing all snubber examinations in a single outage.

#### **VISUAL EXAMINATION**

- ▶ Sites have completed remote examination of snubbers utilizing poles and cameras thereby eliminating costly scaffolds and dose.
- ► Sites not on OMN-13 have incorporated into their procedures the performing of examinations on a snubber anytime it is removed from service for any reason.

#### **TESTING**

- ▶ One utility includes the immediately adjacent snubbers to a failed snubber as part of their scope expansion, even if those snubbers are not in the same DTPG.
- ► Some sites utilize the pre-outage window allowed in ISTD to start testing campaigns prior to the start of the outage.

#### **TESTING**

- ► Some sites have a document that explains how a failed snubber affects the plant until it is restored to operable status.
- ▶ Utilize testing of new snubbers when the snubber arrives on site to create a baseline test on the owner's test bench. This not only provides a baseline for comparison in the future, but may provide indications of test bench anomalies.

#### **SERVICE LIFE MONITORING**

- ▶ End of life testing can be performed on snubbers being removed from service for rebuild or end of useful life to demonstrate the adequacy of their service life, show the current service life may be in need of reduction, or to provide data to support a possible extension.
- ▶ ISTD-6400 requirements are being performed every outage on a portion or all of the snubbers in the large bore snubber population.

#### **SERVICE LIFE MONITORING**

- ► Seal life extensions were completed by multiple utilities to extend the life of snubbers in different applications.
- ► Sites have used hand-stroking as an acceptable method of extending the service life of a mechanical snubber by periodically redistributing the grease.
- ▶ Sites have a maximum service life allowed before a mechanical snubber removed for testing can be reinstalled without regreasing.

#### **NON-SAFETY SNUBBERS**

- Some sites include the non-safety snubbers when 100% visual examinations are being conducted leveraging the resources on site at that time to monitor this population.
- ▶ Some site have started testing a portion of their non-safety snubbers every outage. Sites have replaced the elastomer rod end seals on their large bore snubbers with longer life seals to be able to align the seal replacements with testing activities on a generally rotational basis.

# **DISCUSSION**

What have we missed?

# SNUG 2024 Presentation BOP Snubbers Turbine Stop & Control Valve Issues

Ed Dundon

Millstone Power Station

#### Millstone Unit 2

- Series of Power Uprates
  - Turbine modification
  - Generator rewind
  - Instrumentation margin reduction

#### Millstone Unit 2 BOP Snubbers

Program did not originally test of non-safety snubber.

Many of these snubbers were never serviced since construction.

Non-safety related snubbers were installed by the AE to mitigate normal plant transients such as:

- Relief valve actuation
- Fast closure of control and stop valves

Examples are Turbine Control & Stop Valves, Intermediate Stop/Control Valves, Heat Exchanger relief valves.

These snubbers can be dynamically challenged each cycle.

Whereas most safety related snubbers are to mitigate a seismic event that may never get challenged.

# Current BOP program


- Monitor & tests on 10% of the population.
- No scope expansion
- Problems are captured & resolved via station CR program
- We used the same Service Life for BOP snubbers & Safety Related snubber
- We used a drop & swap program
- All snubbers are treated as safety-related.

# Summary of BOP finding

- Lack of grease
- Dried grease
- Excess wear
- Loose parts
- Alignment between snubber & pipe clamp
- Low fluid levels & fluid leakage

# Recent History on Degraded Support

Condition Reports		Description	Date
•	CR1227352	Unit 2, The clamp for (NSR) snubber M2HGR-490001B shoube redesigned	ld 05/05/2023
•	CR1227290	Unit 2, Missing Spacer on Pipe Clamp 490001B	05/05/2023
•	CR1226814	M2HGR-490001B has a loose pipe clamp hardware	05/02/2023
•	CR1211038	Main Steam Hanger M2HGR-490001B has a loose stud.	10/23/2022
•	CR1146054	M2HGR-490001B hardware shows signs of excessive wear	05/02/2020
•	CR1067827	Identified a loose fastener on pipe hanger 490001B	05/08/2017



· 26002 SH3

# Basis for a Design Change to M2HGR-490001B

# Consequence of not implementing this modification:

- The current design challenges the functionality of a non-tech snubber
   M2HGR-490001B. This snubber is downstream of the B Turbine Control Valve on the 28" HP steam line to the Main HP Turbine.
- Failure of the bolting for the clamp could impact the function of the snubber to restrain MS pipe moment during a Turbine-Generator Trip or a seismic event. Unrestraint MS pipe movement would introduce increased pipe stress and loading in the attached pipe and possibly the HP Turbine inlet nozzle.

#### Bridging Strategy until implementation of permanent fix?

- Currently we are inspecting this pipe snubber each refueling cycle and repairing/replacing as needed.
- Clamp spacers, nuts, pins and loading studs are available. A new clamp and pad eye is not a stock or off the shelf item.

041724

# Revised design for M2HGR-491000B

#### **Recommended Solution**


Repair Option	Justification	Cost Breakdown
DC for removal of shim under the beam	<ul> <li>Eliminates the need for additional inspections with the return to normal inspection</li> </ul>	Labor – 24+ hrs. each inspection Scaffold - \$6000 each inspection
attachment w/new Pad Eye .	frequency of every 18 years. •Eliminate the need to build scaffolding on routine basis for inspection & repair	Material costs -\$11000 new padeye Civil Engineering - 40 hrs Drawings — 20 hrs



Welcome!

# Welcome!







# Snubber Visual Examinations

Presented by Scott Esposito

Patrick Peterson, Division Manager, Iddeal Concepts Inc.

Why Do We
Perform
Snubber
Visual
Examinations?

What Are
We Looking
for During
the PSI?

What Are We
Looking for
During the
Inservice
Inspection?

#### Why Do We Perform Snubber Visual Examinations?

- It is required by the Plant Operating License (Tech Specs or TRM)
- It is the Law
  - 10CFR50.55a
- To ensure Operational Readiness of the Snubber on safety-related systems
- ISTA-1100(c) dynamic restraints (snubbers) used in systems that perform one or more of the three functions:
  - shutting down a reactor to the safe shutdown condition, or
  - · maintaining the safe shutdown condition, or
  - mitigating the consequences of an accident], Or
  - ensure the integrity of the reactor coolant pressure boundary
- Snubbers in these systems are considered Safety-related or Safety Significant
  - Safety Significant = Outside of ASME Class 1, 2, or 3 boundary, but meets the requirement of ISTA-1100(c).

# What Are We Looking for During the Preservice Examination?

- Preservice Examination or Inspection (PSI)
  - What does "Pre-Service" mean During initial plant startup or for new and modified systems
    - Thermal Movement
    - Incremental Movement Verification
    - Total Movement Verification

# What Are We Looking for During the Preservice Examination?

- No visible signs of damage or impaired operational readiness exist as a result of storage, handling, or installation.
- The snubber load rating, location, orientation, position setting, and configuration (e.g., attachments and extensions) are in accordance with design drawings and specifications.
- Adequate swing clearance is provided to allow snubber movement.
- If applicable, fluid is at the recommended level, and fluid is not leaking from the snubber system.
- Structural connections, such as pins, bearings, studs, fasteners, lock nuts, tabs, wire, and cotter pins, are installed correctly.

# What Are We Looking for During the Inservice Examination?

- Inservice Examination or Inspection (ISI)
  - What does "Inservice" mean All examinations of the currently installed snubbers, after plant startup
    - Physical damage,
    - Leakage (if applicable),
    - Corrosion, or
    - Degradation from environmental exposure or operating conditions


# What Are We Looking for During the Inservice Examination?




Bent Snubber

End Connecto r











Spherical Bearing dis-engaged




Spherical Bearing dis-engaged







## What Are We Looking for During the Inservice Examination?





- Snubber examinations were included in ASME Section XI as part of the plant ISI Program, including updates to the ISI Programs
  - ASME Code 1983 Edition thru 2006 Addenda:
    - IWF-5300 INSERVICE EXAMINATIONS AND TESTS
      - (a) Inservice examinations shall be performed in accordance with ASME/ANSI OM, Part 4, using the VT-3 visual examination method described in IWA- 2213.
    - IWF-5400 REPAIR/REPLACEMENT ACTIVITIES
      - Repair/replacement activities performed on snubbers shall be in accordance with IWA-4000. Snubbers installed, corrected, or modified by repair/replacement activities shall be examined and tested in accordance with the applicable requirements of IWF-5200 prior to return to service.

- IWF-5300 states that in-service examinations shall be performed in accordance with ASME/ANSI OM, Part 4.
  - ASME/ANSI OM, Part 4, 2.0, 1988 Edition included;
    - Preservice Examinations
      - Preservice Thermal Movement Examination
    - Inservice Examinations
      - Requirements
      - Frequency
      - Sample Size
      - Failure Evaluation
      - Corrective Action and Impact on Examination Frequency
    - Examination Documentation

#### •10CFR50.55a

- 50.55a(b)(3)(v) ...Article IWF-5000, "Inservice Inspection Requirements for Snubbers," of the
  ASME BPV Code, Section XI, must be used when performing in-service inspection examinations
  and tests of snubbers at nuclear power plants, except as conditioned in paragraphs (b)(3)(v)(A)
  and (B) of this section.
- (b)(3)(v)(A) ...Licensees <u>may use</u> Subsection ISTD, ASME OM Code, 1995 Edition through the latest edition and addenda in place of the requirements for snubbers in the editions and addenda <u>up to the 2005 Addenda</u> of the ASME BPV Code, Section XI, IWF-5200(a) and (b) and IWF-5300(a) and (b). Preservice and inservice examinations must be performed using the VT-3 visual examination method described in IWA-2213.
- (b)(3)(v)(B) ...Licensees **must comply** with the provisions for examining and testing snubbers in Subsection ISTD of the ASME OM Code and make appropriate changes to their technical specifications or licensee-controlled documents <u>when using the 2006 Addenda and later</u> editions and addenda of Section XI of the ASME BPV Code.

- Plants that have updated to the ISI/IST program to ASME Section XI, 2007 and later and the OM Code, 2001 thru current Edition, MUST use ISTD.
- 10CFR50.55a ties the OM (ISTD) to ASME Section XI ISI Program update requirements
  - 50.55a(f)(4) [Inservice testing standards requirement for operating plants] and 50.55a(g)(4) [Inservice inspection standards requirement for operating plants]

## Additional Code Requirements that Require Visual Examination

- ISTD-1600 Snubber Modification and Replacement Snubber replacement activities shall be performed in accordance with Section XI of the ASME Boiler and Pressure Vessel Code, as applicable.
  - The term repair/replacement activity includes those activities known as repair, replacement, modification, or, alteration. Reasons for repair/replacement activities may include the following:
    - (a) discrepancies detected during inservice inspection, maintenance, or service
    - (b) regulatory requirements change
    - (c) design changes to improve equipment service
    - (d) changes to improve reliability
    - (e) damage
    - (f) Failure during service
    - (g) personnel exposure
    - (h) economics
    - (i) end of service life
    - (j) addition of new items or system

## Additional Code Requirements that Require Visual Examination

- ASME Section XI, IWA-4000, Repair/Replacement Activities
  - The term repair/replacement activity includes those activities known as repair, replacement, modification, or, alteration. Reasons for repair/replacement activities may include the following:
    - (a) discrepancies detected during inservice inspection, maintenance, or service
    - (b) regulatory requirements change
    - (c) design changes to improve equipment service
    - (d) changes to improve reliability
    - (e) damage
    - (f) Failure during service
    - (g) personnel exposure
    - (h) economics
    - (i) end of service life
    - (j) addition of new items or system

## Additional Code Requirements that Require Visual Examination

#### ASME Section XI, IWA-4132, Items Rotated from Stock

- For snubbers rotated from stock and installed on components (including piping systems), the following requirements may be used in lieu of all other requirements of IWA-4000, provided the rotation is only for testing or preventive maintenance of the removed items:
  - (a) Items being removed and installed shall be of the same design and construction
  - (b) Items being removed shall have no evidence of failure at the time of removal
  - (c) Items being rotated shall be removed and installed only by mechanical means
  - (d) Items being installed shall previously have been in service
  - (e) The Owner shall track the items to ensure traceability of inservice inspection and testing records
  - (f) Use of an Inspector and an NIS-2 form are not required
  - (g) Repair/replacement activities on removed items shall be performed in accordance with the requirements of this Article [IWA-4000].

- Plants that have updated to the ISI/IST program to the OM Code, 2001 thru current Edition, MUST use ISTD.
  - ISTD-4100 Preservice Examination For operating plants implementing Subsection ISTD, these requirements shall not be applicable if preservice examinations have been performed.
    - ISTD-4110 Preservice Examination Requirements
    - ISTD-4120 Reexamination
    - ISTD-4130 Preservice Thermal Movement Examination Requirements
    - ISTD-4140 Preservice Examination Corrective Actions

- OM Code, 2001 thru current Edition
  - ISTD-4200 Inservice Examination
    - ISTD-4220 Snubber Categorization
      - Typically Accessible or Inaccessible; Inside Containment or Outside Containment
    - ISTD-4230 Visual Examination Requirements
    - ISTD-4240 Operational Readiness Test Evaluation
    - ISTD-4250 Inservice Examination Intervals
    - ISTD-4260 Inservice Examination Sample Size
    - ISTD-4270 Inservice Examination Failure Evaluation
    - ISTD-4280 Inservice Examination Corrective Action

## Snubber Visual Examinations: Examination Frequency

- ISTD-4250 Inservice Examination Intervals
  - Table ISTD-4252-1 Visual Examination Table
    - Once per Fuel Cycle (up to 24 months)
      - "The basic interval shall be the normal fuel cycle up to 24 mo.
    - Maximum of two fuel cycles (48 Months)
      - "The examination interval may be as great as twice"
    - OMN-13, Each snubber at least once every 10 years

# Snubber Visual Examinations: Examination Frequency

- •ISTD-4250 Inservice Examination Intervals
  - Based on Safety/Safety Significant Snubber Population and number of failures during the current interval, the Examination Frequency may change.
    - The "current" interval is the "basic interval" [one fuel cycle], or maximum interval [two fuel cycles], or OMN-13 implementation [10-year interval]
  - Scope Expansion for Visual Examination failure is not required, unless the number of failures during the current interval exceed Table ISTD-4252-1.

- Personnel Qualifications
  - Visual Examiners and Reviewers
    - Owner Specified Qualifications
      - ISTA-1500 Owner's Responsibilities; (e) qualification of personnel who
        perform and evaluate examinations and tests in accordance with the
        Owner's quality assurance program.
    - VT-3 Required for ASME Section XI portion only, (Replacement and End Attachments)

- Tracking and Documenting Examinations
  - ISTD-4210 Method and Objective
    - Inservice examination shall be a visual examination to identify physical damage, leakage, corrosion, or degradation that may have been caused by environmental exposure or operating conditions. External characteristics that may indicate operational readiness of the snubber shall be examined. <u>An examination checklist</u> <u>shall be used.</u> Typical items are listed in Nonmandatory Appendix B of this Division.

# Snubber Visual Examinations: Tracking and Documenting Examinations

- Nonmandatory Appendix B, Dynamic Restraint Examination Checklist Items
  - Pre-service Examination
    - (a) incorrect snubber load rating
    - (b) incorrect installed location
    - (c) incorrect installed orientation
    - (d) incorrect position setting
    - (e) incorrect snubber configuration
    - (f) inadequate swing clearance
    - (g) snubber installed with preset locking screws used for shipment only
    - (h) protective coverings or shipping plugs not removed

- Nonmandatory Appendix B, Dynamic Restraint Examination Checklist Items
  - Inservice Examinations
    - (a) inadequate reservoir fluid level
    - (b) loose, missing, or incorrectly installed structural connections or fasteners
    - (c) vented reservoir oriented such that hydraulic fluid cannot gravitate to snubber
    - (d) corrosion or solid deposits that could result in unacceptable snubber performance
    - (e) deformed structural attachment or piston rod
    - (f) weld arc strikes, paint, weld slag, adhesive, or other deposits on piston rod or support cylinder that could result in unacceptable snubber performance
    - (g) spherical bearing not fully engaged in attachment lug
    - (h) inadequate position setting

- Typical Examination Items
  - Mechanical Snubbers Attributes
    - lock wires
    - fillister screws
    - retaining rings (snap rings)
  - Hydraulic Snubbers Attributes
    - Fluid Connections
    - Fluid Level
    - Leakage




## Iddeal Concepts, Inc.

Intelligent. Innovative. Iddeal.

### SnubbWorks

An Integrated Inspection Management System

### Schedule Locations



### Schedule Locations

- Scheduler
  - Schedule the locations for visual examination
  - Add WO's (As-Found and As-left)

□ SnubbWorks® - Outage / Work Scope Scheduler											×
Scheduler										SNUG 2024 <none> 135</none>	
∠ Exam I →	Mark No →			TPNS No →			-,	Work De 🗸	AF WO -		RR Sct 🔺
		M20249	10074	Model: PSA-1		N/A	MS	Inspect	Add AF WO/Task	Add AL WO/Task	
1074	MS-H-52	M20250	10080	Model: PSA-1		N/A	MS	Inspect			
1097		M20344	10119	N/A	Yes	N/A	MS	Inspect			
1083		M20332	1090	Model: PSA-1		N/A	MS	Inspect			
1105		M20401	11275	Model: PSA-3		W1140	NB	Inspect			
1040	HPCI-H-303	M20345	12434	Model: PSA-3		M448	HPCI	Inspect			
1090		M20126	12672	Moder, PSA-1		M807	MS	Inspect			
1119		M20131	12681	Model: PSA-1		M816	RC	Inspect			
1114	RC-H-554	M20143	12709	Model: PSA-1		M724	RC	Inspect			
1086	MS-H-624	M28153	12733	Model: PSA-1	No	M796	MS	Inspect			
1075	MS-H-521	M20155	12738	Model: PSA-1	No	M683	MS	Inspect			
1088	MS-H-626	M20158	12741	Model: PSA-1	No	M798	MS	Inspect			
1073	MS-H-517	M20059	13155	Model: PSA-1	No	M679	MS	Inspect			
1641	MS-H-696	M20060	13156	Model: PSA-1	No	M868	MS	Inspect			
1113	RC-H-550	M20065	13163	Model: PSA-1	No	M719	RC	Inspect			
1109	PC-H-672	M20068	13167	Model: PSA-1	Yes	M844	PC	Inspect			
1103	NB-H-1	M20069	13169	Model: PSA-1	No	M1	NB	Inspect			
1110	RC-H-52	M20082	13194	Model: PSA-1	Yes	M174	RC	Inspect			
1004	AFW-H-3	M20001	14448	Model: PSA-1	Yes	N/A	AFW	Inspect			
1131	RHR-H-245	M20366	15291	Model: PSA-3	No	M390	RHR	Inspect			
1143	SI-H-111	M20368	15349	Model: PSA-3	No	N/A	SI	Inspect			
1142	SI-H-107	M20369	15765	Model: PSA-3	Yes	N/A	SI	Inspect			
1072	MS-H-51	M20370	15767	Model: PSA-3	Yes	N/A	MS	Inspect			
1067	MS-H-481	M20335	1580	Model: PSA-1	No	M641	MS	Inspect			-
1			1						•	-	F
V/	%% <b>↑</b> ↓[										×















### OMN-13 Tracking


- Last Visual Examination (Last AF Date)
  - The database will show the last time a datasheet was created for each location (Safety, Safety Significant, and Non-Safety)
- Next Visual Examination (Next AF Date)

DATASHEETS

- The database will show the due date for the next examination, Last AF date plus 10 years) for each location (Safety, Safety Significant, and Non-Safety)
- If the components are scheduled in the current outage, the "As-found" column will have "Yes" and the VT Scope column will have a Work Scope displayed

## OMN-13 Tracking

- 1. Planner;
- 2. Visual Inspection
- 3. Select the "Previous Locations AF Visuals" icon




## OMN-13 Tracking

SnubbWorks®							_ ×	
Previous As Found Visuals  Work Scope: Current Filter: <no. 172<="" found:="" records="" td=""><td>&gt;</td><td></td></no.>							>	
∠ Mark No →	Exam No - Serial No -	Current Serial No 💂	Last AF Date - Last AF Resul -	Next AF Date -	As Found 🗸	VT Scope -	ASME Class -	T
AFW-H-118	1001 730015	36563	10/30/2010 S	10/30/2020	Yes		2	F
AFW-H-118	1001 730015	36563	10/30/2010 S	10/30/2020	Yes	100%	2	F
AFW-H-13	1002 18196	18196	10/29/2012 S	10/29/2022	Yes	100%	2	F
AFW-H-13	1002 18196	18196	10/29/2012 S	10/29/2022	Yes		2	F
AFW-H-2	1003 24452	24452	4/28/2011 S	4/28/2021	Yes	100%	3	I
AFW-H-3	1004 12743	14448	3/27/2012 S	3/27/2022	Yes	100%	3	I
AFW-H-4	1005 24453	24453	4/28/2011 S	4/28/2021	Yes	100%	3	1
AFW-H-5	1006 20959	20924	10/31/2010 S	10/31/2020	Yes	100%	3	1
BS-H-370	1007 750102	720115	10/5/2007 S	10/5/2017	Yes	100%	2	7
CF-H-549	1008 22400	720105	10/31/2010 S	10/31/2020	Yes	100%	1	(
CS-H-260	1009 6828	8464	3/27/2012 S	3/27/2022	Yes	100%	2	(
CS-H-287	1010 810149	830024	4/8/2012 S	4/8/2022	Yes	100%	2	(
CVCS-H-18	1011 20880	20880	5/9/2011 S	5/9/2021	Yes	100%	1	F
CVCS-H-22	1012 24449	24449	5/6/2011 S	5/6/2021	Yes	100%	1	F
CVCS-H-23	1013 11266	25432	11/3/2010 S	11/3/2020	Yes	100%	2	F
CVCS-H-24	1014 16541	16541	4/26/2011 S	4/26/2021	Yes	100%	2	F
CVCS-H-25	1015 9483	9483	5/3/2011 S	5/3/2021	Yes	100%	2	F
DH-H-380	1016 820014	760027	4/3/2012 NA	4/3/2022	Yes	100%	2	1
DH-H-544	1017 730216	730216	10/6/2007 S	10/6/2017	Yes	100%	2	L
DH-H-582	1018 19909	720098A	3/29/2012 S	3/29/2022	Yes	100%	2	L
DH-H-582	1018 19909	720098A	3/29/2012 S	3/29/2022	Yes		2	L
DH-H-590	1019 13156	720130	10/30/2010 S	10/30/2020	Yes	100%	3	٧
EF-H-379	1020 9866	760108	10/9/2007 S	10/9/2017	Yes	100%	4	E
EF-H-379	1020 9866	760108	10/9/2007 S	10/9/2017	Yes		4	E
FW-H-125	1021 2500-10-152	2500-10-152	5/3/2011 S	5/3/2021	Yes	100%	2	F
FW-H-126	1022 2500-10-153	2500-10-153	5/5/2011 S	5/5/2021	Yes	100%	2	F
FW-H-127	1023 G15200-1	G15200-1	5/6/2011 S	5/6/2021	Yes		Q	7-
4								

### Create Data Sheets - Tech Spec 1

- 1. Datasheets;
- 2. Visual Exam Records
- 3. TechSpec1
  - TechSpec1 –
     Designed to cover
     the OM Code
     Examination
     Boundary



SnubbWorks® - T	ech Spec Visual I	nspection Rep	ort							
As Found	As Left	PSI								
Plant/Unit: DE1 / Outage No.: SNUG 2024										
Procedure No.:		Revisi	on No.:	Rep	Report No.:					
Exam No.:		Buildin	g/Room:							
Mark/Hanger No:										
System:	Elevation:				Manufacturer:					
Line No.:	Row/Col.				Model:					
WO/WR No.:		Map N	0.:		Size:					
Resolu	Resolution Techniq			Lighting	Tools					
Other - See Comme	Other - See Comments			~		V				
GENERAL : Component support is	dentified	Sat	Unsat N/A	LINKAGE CONNECTION Attachment items not	LINKAGE CONNECTIONS / ATTACHMENTS: Sat Unsat					
Component installed		_	0 0		/ connections not loose	0 0 0				
FLUID CONNECTION		0	J 9		er pins / load pins / snap ring					
Fluid connections and		ina ^	0.6	No Loose / missings p		0 0 0				
Assembly / valve blo		- 0	0 0	Close tolerance surfa		0 0 0				
Piston rod and assoc		0	0 0	1	ding / excess movement	0 0 0				
Reservoir sightglass	/ cracks / leaking	Õ	0 0	End attachment gaps		0 0 0				
Reservoir shipping pl	-	0	$\circ$	SNUBBER MEASURE						
Reservoir orientation		0	$\circ$	System Temperature:	O Hot O Cold					
Fluid clarity / no susp	ended solids	0	0 0	Piston Rod Setting:						
Fluid Level: Pin to Pin Setting:										
				Supplemental data att	tached: Yes	<ul><li>No</li></ul>				
Comments:										
Examiner Name				Level	Exam Date:					
Examiner Name				Level	Exam Date:					
EXAMINATION EVA	LUATION AND OV	ERVIEW				Sat Unsat N/A				
There are no signs o						000				
Attachments to the s						0 0 0				
		bber to the con		to the snubber are function	nal.	0 0 0				
OVERALL RESULTS		Ш	DEGRADED							
NCR/AR/CR Issued:			wo	O/WR Issued:						
EVALUATION COMMENTS:										
Reviewed By: Level Date										
Reviewed By:										
€€€	<b>€</b>			d 🌣 🛦 🥞 🛚		<b>= X</b>				


Test Plant Unit 2 Report No: SNUG 2-VT3-0001 Page 1 of 1

Plant/Unit: DE1 / 1	Out	age No:	SNUG 2024	As Foun	d 🔾 As	Left (	PSI
Procedure No: PROC-003	Rev	ision:	1	WO/WR No: N	I/A		
Exam No: 1002 Bu	ilding/Room:	RB / N/A	Ą	Component No:	M20371		
Mark No: AFW-H-13				Serial No:	18196		
System: AFW Ele	evation:	289'		Manufacturer:	Mechanical	ı	
Line No: Safety Ro	w/Column:	N/A		Model:	PSA-3		
TPNS No: Model: PSA-3 Ma	ap No:	N/A		Size:	3		
Resolution	Technique		Lighting		Tools		
Other - See Comments							
GENERAL:  Component support identified  Component installed / or ientaled per design  FLUID CONNECTIONS:  Fluid connections and seals loose / leaking Assembly / valve block / body / fittings leaking Pis ton rod and ass ociated seal Reservo's sightglass / cracks / leaking Reservo's hipping plug not installed Reservo's rientation / vent port at top Fluid clarity / no suspended solids Fluid Level:  Comments:	Sat Uns.  O O O O O O O O O O O O O O O O O O O	at N/A	LINKAGE CONNEC Attachment items ni Snubber attachmen Broken / missing oo No loose / missings Close tolerance suri Anchor points for bit End attachment gas SNUBBER MEASU System Temperatur Pis bn Rod Setting: Pin to Pin Setting: Supplemental data	ot bent / damaged ts / connections no tter pins / load pins parts / loaknuts face / corrosion ndling / excess mov as and tolerances  REMENT S: e:	/ deformed it loose s / snap rings vement	Sat Uns.	<ul><li>0</li><li>0</li><li>0</li><li>0</li><li>0</li></ul>
Examiner Name:			Level:	Exam Date			
Examiner Name:			Level:	Exam Date			
EXAMINATION EVALUATION AND OVERVIEW	W				5	Sat Unsat N	I/A
There are no signs of damage or impaired oper	rability.					00	o
Attachments to the supporting structure are see	cure.					00	
Fasteners for the attachment of the snubber to	the component	and to th	ne snubber are function	al.		00	o
OVERALL RESULTS: SAT	DEGRAD	DED	UNSAT				
NOA/AR/CR Issued:		WO/WR	Issued:				
EVALUATION COMMENTS:							
Reviewed By:				Level:	Date:		

### Create Data Sheets – Tech Spec 2

- 1. Datasheets;
- 2. Visual Exam Records
- 3. TechSpec2
  - TechSpec2 –
     Designed to cover


     ASME Section XI
     and OM Code
     Boundaries



SnubbWorks® - Tech Spec Visual	Inspection Report											est Plant Unit 2	
As Found As Left	□ PSI					Sn	ubber Vis	ual E	xamination	ו '	Report No: SM	IUG 2-VT3-0002 Page 1 of 1	
Plant/Unit: DE1 /	Outage No.: SNUG 2	024										Page 1 of 1	
Procedure No.:	Revision No.:	Report No.:		1 - 1	Plant/Unit	DE1 / 1	Outage	No: S	SNUG 2024	<ul><li>As Found</li></ul>	○ As Lef	t () PSI	
Exam No.:	Building/Room:		Comp No.:		Procedure No	x PROC-003	Revisio	n: 1	i	WO/WR No:	N/A		
Mark/Hanger No:	building/Room.		Serial No:			11100000		<u>-</u>	'	- 110/11/11/11/11	1075		
System:	Elevation:		Manufacturer:		Exam No: 10	003	Building/Room:	IB / N/A	A	Component No:	M20031		
Line No.:	Row/Col. No.	M	Model:		Mark No: Ai	FW-H-2				Serial No:	24452		
WO/WR No.:	Map No.:	S	Size:		_	FW	Elevation:	253'		Manufacturer:	Mechanical		
Resolution	Technique	Lighting	Tools				_			Model:			
Other - See Comments				$\overline{v}$	Line Type: Si		Row/Column:	N/A			PSA-1		
Strict 2 See Comments	V			V	WO/WR No.N	/A	MapNo:	N/A		Size	1		
	Sat Unsat N/A			Sat Unsat N/A		Resolution	Technique		Lighting	1	ools		
Component support identified	$\circ \circ \bullet$	Movement obstructions		0 0 0	Other - See (	Comments							
Component installed / orientated per de	lesign O O	Close tolerance surface	/ corrosion	0 0 0		•	Sat Unsa	t N/A	•		Sat	Unsat N/A	
No signs of physical damage	○ ○ ●	Corrosion / material / scr	ratches on piston rod	0 0 •		support identified	0 0		Movement obstruction	IS	0	0 🐵	
Structural steel attachments / embedm	. 000	Reservoir sightglass		0 0 0		installed / orientated per desig			Close tolerance surface	ces / comosion	ion 🔾 🔾 📵		
Attachment items not bent / damaged /	0 0 0	Fluid connections and se		0 0 0		ohysical damage	00	•		/ scratches on piston rod O O			
Snubber attachments / connections no	0 0 0	Assembly / valve block / body / fittings leaking		0 0 0		eel attachments / embedment							
Broken / missing cotter pins / load pins		Reservoir shipping plug not installed Vent not obstructed or damaged		0 0 0		tems not bent / damaged / de chments / connections not loc		<ul><li>●</li><li>I</li></ul>	Assembly / valve bloc	nd seals loose / leaking ( ) ( )		0 0	
No signs of weak, stripped threads No loose / missing parts / locknuts	0 0 0	Reservoir orientation / ve	-	0 0 0		sing cotter pins / load pins / si		·	Reservoir shipping plu		\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	0 0	
Supporting structure and foundations	0 0 0	Fluid clarity / no suspend		0 0 0	No signs of v	neak, stripped threads		ě	Vent not obstructed or		ŏ	ŏ ĕ l	
Concrete anchors	0 0 0	Fluid clarity / no suspended solids  Fluid Level:			No loose / mi	No loose / missing parts / locknuts							
No cracked / chipped concrete / grout													
Weld integrity		Pin to Pin Setting:				Concrete anchors O O Fluid Level:							
Spherical bearings functional	0 0 0	Piston Rod Setting:				chipped concrete / grout	0 0	•	Pin to Pin Setting:				
End attachment gaps and tolerances	0 0 0	System Temperature: O Hot O Cold			Weld integrity	-	0 0		Piston Rod Setting:				
Anchor points for binding / excess mo		Supplemental data attac	ched: ( Yes (	No		arings functional	0 0	•	System Temperature:	O Hot ® 0	old		
						ent gaps and tolerances	0 0	•	•		_		
Comments:					Anchor points	s for binding / excess moveme	ent O O	•	Supplemental data att	ached: O	′es 🖲 N	0	
Examiner Name		Level	Exam Date:		Comments								
Examiner Name			Exam Date:										
		, Level			Examiner Na				Lev		n Date:		
EXAMINATION EVALUATION AND OV				Sat Unsat N/A	Examiner Na				Lev	/el: Exai	n Date:		
There are no signs of damage or impair				0 0 0		N EVALUATION AND OVER					Sat	Unsat N/A	
Attachments to the supporting structure				0 0 0	There are no	There are no signs of damage or impaired operability.						0 0	
Fasteners for the attachment of the sn				000								0 0	
OVERALL RESULTS: SAT	DEGRADED	UNSAT			Fasteners for the attachment of the snubber to the component and to the snubber are functional.  OVERALL RESULTS: SAT DEGRADED UNISAT						0 0		
NCR/AR/CR Issued:	NOA/AR/CR I			WO/WR									
EVALUATION COMMENTS:						N COMMENTS:		WO/WK	issued:				
Reviewed By:	V	Reviewed By	r:				Level:	Date:					
Reviewed By:		Reviewed By						Date:					
	~	Date			- Reviewed by						Date.		
$(\mathbf{k}(\mathbf{c})\mathbf{c})\mathbf{c}$		*** 🔥 🕞 🔓	用前 🖺 🖶	, 📖 🗶									


### Create Data Sheets - Tech Spec 3

- 1. Datasheets;
- 2. Visual Exam Records
- 3. TechSpec3
  - TechSpec3 –
     Designed to cover
     OM Code
     Boundaries.
     Requires "Settings"
     to be populated for auto calculations of allowable Piston
     Settings



SnubbWorks® - Tech Spec Visual I	nspection Report											st Plant Unit 2
As Found As Left	PSI					5	Snubber	' Visual	Examinatio	n	Report No: SNU	
Plant/Unit: DE1 /	Outage No.: SNUG 2	024										Page 1 of 1
Procedure No.:	Revision No.:	Report No.		1-1	Plant/Unit	DE1 / 1		Outage No:	SNUG 2024	As Found	○ As Left	O PSI
Exam No.:	Building/Room:		Comp No.:		Procedure	lo: PROC-003		Revision:	1	WO/WR No:	N/A	
Mark/Hanger No:	Building/Room.		Serial No:		Troccane	11.00-000		KCVISIOII.	<u>.                                      </u>		N/A	
System:	Elevation:		Manufacturer:		Exam No:	1003	Building	g/Room: IB /	N/A	Component No:	M20031	
Line No.:	Row/Col. No.		Model:		Mark No:	AFW-H-2				Serial No:	24452	
WO/WR No.:	Map No.:		Size:		System:	AFW	Elevatio	on: 253	ę.	- Manufacturer:	Mechanical	
Resolution	Technique	Lighting	Tools		Line Type:		Row/Co			Model:	PSA-1	
Other - See Comments	_	~		$\overline{v}$	WO/WR No		Map No	_		_ Note:	1	
					WO/WR NO						1	
	Sat Unsat N/A		S	at Unsat N/A		Resolution	Technic	que	Lighting	1	Tools	
Component support identified	0 0 •	Movement obstructio	ns	000	Other - Se	e Comments						
Component installed / orientated per de		Close tolerance surfa		$\circ$ $\circ$ $\bullet$				Sat Unsat N/A	\ \		Sat U	nsat N/A
No signs of physical damage	○ ○ ●			○ ○ ●	Componen	t support identified	{	0 0 👁	Movement obstruction	ons		0 0
Structural steel attachments / embedme	. 000	Reservoir sightglass		0 0 0		t installed / orientated per d		000	Close tolerance sur		0 (	0 💿 📗
Attachment items not bent / damaged /	~ ~ ~			0 0 0		f physical damage		$\circ$		/ scratches on piston		ŏ 🏽
Snubber attachments / connections no Broken / missing cotter pins / load pins	0 0 9	Reservoir shipping p		0 0 0		teel attachments / embedn titems not bent / damaged		000	Reservoir sightglass	s nd seals loose / leakin		
No signs of weak, stripped threads	/ snap rings O O	Vent not obstructed	-	0 0 0		tachments / connections no		000		ock / body / fittings lea		ŏ 🎳 📗
No loose / missing parts / locknuts	0 0 0	Reservoir orientation			Broken / m	issing cotter pins / load pins		0 0 0	Reservoir shipping p		0 (	Ö 🖲 📗
Supporting structure and foundations	0 0 0	Fluid clarity / no susp		0 0 0		f weak, stripped threads		ŏŏĕ	Vent not obstructed			ୁ 🧕 📗
Concrete anchors	0 0 0	Fluid Level:		0 0 0		missing parts / locknuts structure and foundations			Reservoir orientation			ŏ 🗟 📗
No cracked / chipped concrete / grout	0 0 0	Pin to Pin Setting:			Concrete a			000	Fluid clarity / no sus Fluid Level:	pended solids		
Weld integrity	$\circ \circ \bullet$	Piston Rod Setting:				/ chipped concrete / grout		ŏŏŏ				~ ~
Spherical bearings functional	0 0 0	System Temperature	: ( Hot ( Cold		Weld integ	rity		000	Pin to Pin Setting:			
End attachment gaps and tolerances  Anchor points for binding / excess more	0 0 0	Supplemental data a	ttached:  Yes  6	) No	Spherical I	earings functional	(	000	Piston Rod Setting:			
Anchor points for binding / excess mo	vement O O	Supplemental data a	macried. Tes	) NO	End attach	ment gaps and tolerances	4	000	System Temperatur	e: 🔾 Hot 📵 (	Cold	
Comments:					Anchor poi	nts for binding / excess mo	vement	$\circ \circ \circ$	Supplemental data	attached: O	Yes 🖲 No	
Examiner Name Examiner Name	V	_	Exam Date:		Comment							
	~	Level			Examiner						m Date:	
EXAMINATION EVALUATION AND OV	ERVIEW		S	Sat Unsat N/A	Examiner	lame:			L	evel: Exa	m Date:	
There are no signs of damage or impair	ed operability			000	EXAMINAT	ON EVALUATION AND O	VERVIEW				Sat U	nsat N/A
Attachments to the supporting structure	e are secure			000	There are	There are no signs of damage or impaired operability.					0 0	
Fasteners for the attachment of the snu	ubber to the component and to t	the snubber are function	nal.	000	Attachme	Attachments to the supporting structure are secure.					0 0	
OVERALL RESULTS: SAT DEGRADED UNSAT					Fasteners	Fasteners for the attachment of the snubber to the component and to the snubber are functional.					00	
CRIARICR Issued: WO/WR Issued: OVE RALL RE SULTS: SAT DEGRADED UNSAT												
EVALUATION COMMENTS:					NOA/AR/CF	Issued:		WOA	WR Issued:			
					EVALUATIO	ON COMMENTS:						
Reviewed By:	~	Level Date			Reviewed	Ву:				Level:	Date:	
Reviewed By:	~	Date			Reviewed	By:					Date:	
<b>(€(€(3)3)</b>		* <u> </u>		<b>=</b> ×								

#### Settings needed for Tech Spec 3



Tech Spec3	Test Plant Unit 2  Snubber Visual Examination Report No: SNUG 2-VT3-0003
	Page 1 of 1
Procedure No.: PROC-003	
Exam No.: 1004 Building/Room: N/A Comp No.: M20001	Procedure No: PROC-003 Revision: 1 ® As Found As Left PSI
Mark/Hanger No: AFW-H-3 Serial No: 14448	Location: IB 253' Building/Room: IB / N/A Component No: M20001
System: AFW Elevation: 253' Manufacturer: Mechanical	Mark No:         AFW-H-3         Serial No:         14448
Line No.: Safety Row/Col. No. N/A Model: PSA-1	System: AFW Elevation: 253' Manufacturer: Mechanical
WO/WR No.: N/A Map No.: N/A Size/Stroke: 1 / 4	Line No: Safety RowColumn: N/A Model: PSA-1
Resolution Technique Lighting Tools	WO/WR No: N/A Map No: N/A Size/Stroke: 1/4
Other - See Comments	Resolution Technique Lighting Tools
	Other - See Comments
EL UID COUNTESTIONS	Unier - See Cultiments
FLUID CONNECTIONS: Sat Unsat N/A SNUBBER MEASUREMENTS:	FLUID CONNECTIONS: Sat UnsatN/A SNUBBER MEASUREMENTS: Cold
Fluid connections and seals loose / leaking Ool	Fluid connections and seals loose / leaking 🔘 🔘 Design Piston Set 2.5 As Measured 2.5
Assembly / valve block / body / fittings leaking O Design Piston Set 2.75 As Measured 2.5	Assembly / valve block / body / fittings leaking 🔘 🕒 Zero Adjustment 0 Them. Move(C) 0
Piston rod and associated seal  O O E Zero Adjustment  O Therm. Move(C)	Piston rod and associated seal Recorded Setting 2.5 Therm. Move(T) 0.875
Reservoir sightglass / cracks / leaking	Reservoir sightglass / cracks / leaking
LINKAGE CONNECTIONS / ATTACHMENTS:  Available Movement (C) 0.5 < 2.500 < 4.5	Fluid Level
Attachment items not bent / damaged / deformed Available Movement (T) 0.5 < 3.375 < 4.5	LINKAGE CONNECTIONS / ATTACHMENTS:
Snubber attachments / connections not loose Available Movement Acceptable	Attachment items not bent / damaged / deformed
Broken / missing cotter pins / load pins / snap rings	Snubber attachments / connections not loose  For Cold P liping: 0 < [as-measured - the "Zero adjustment"]
No Loose / missings parts / locknuts	Broken / missing cotter pins / load pins
Close tolerance surface / corrosion	No Loose / missings parts
Anchor points for binding / exces movement	Close tolerance surface / corrosion  Anchor points for binding / excess movement  Anchor points for binding / excess movement
End attachment gaps and tolerances	Anchor points for binding / excess movement
Other O •	Other Control of the
Comments:	Comments
Examiner Name	Examiner Name: Level: Exam Date: Level: Level: Exam Date: Level: Level: Exam Date: Level:
There are no signs of damage or impaired operability	EXAMINATION EVALUATION AND OVERVIEW Sat Unsat N/A
Attachments to the supporting structure are secure	There are no signs of damage or impaired operability
Fasteners for the attachment of the snubber to the component and to the snubber are functional.	Attachments to the supporting structure are secure
	Fasteners for the attachment of the snubber to the component and to the snubber are functional.
	OVERALL RESULTS: SAT DEGRADED DINSAT Supplemental data attached: O Yes O No
CR Initiated: WO/Notification:	
EVALUATION COMMENTS:	CR Initiated: WO/Notification:
	EVALUATION COMMENTS:
Supplemental data attached: Yes   No	Reviewed By: Level: Date:
Reviewed By:   Level Date	Reviewed By:
Reviewed By:	
	<b>1</b>

#### Review Data Sheets

- Datasheet Reviews
  - SAT Meets all of the examination criteria
  - DEGRADED Not fully satisfactory, but still evaluated to functional (i.e., less that 50% fluid); Condition SHOULD be corrected to be fully functional
  - UNSAT Did not meet the functional requirements; Condition MUST be corrected or snubber replaced [ISTD-4280]
  - Schedule UNSAT for Functional Testing


#### Review Data Sheets

EXAMINATION EVALUATION AND OVERVIEW	Sat Unsat N/A					
There are no signs of damage or impaired operability	0 0 0					
Attachments to the supporting structure are secure	0 0 0					
Fasteners for the attachment of the snubber to the component and to the snubber are functional.	0 0 0					
OVERALL RESULTS: SAT DEGRADED UNSAT						
CR Initiated: WO/Notification:						
EVALUATION COMMENTS:						
Supplemental data attached: Yes   No						
Reviewed By:   Level Date						
Reviewed By: Date						
	🖶 🖶 🗷					



- Updating History
  - After the examination datasheets have been reviewed, the History can be updated
  - The information will be captured in three locations:
    - History database
    - Location Database (for the individual Location), and
    - Snubber Database (for the individual Snubber Serial Number)








SnubbWorks®					
History Data					
History Found Left	t Memo				
	SNUBBER	R_ID H10527	Serial No	750046	
	LOCATION	N_ID AFW-H-3	~		
	OUTAGE	_NO RF017	<u> </u>		
	NEW SNUBBER	R_ID	∨ New Serial No		
FT_Date_AF	11/5/2010	FUNC_TEST_AF	SAT V	AF PISTON_SET	
FT_Date_AL		FUNC_TEST_AL	~	AF PIN_TO_PIN	
AF_Date	10/27/2010	AS FOUND VISUAL	SAT	AF RES_LEVEL	
RB_Date		REBUILD		AL PISTON_SET	
AL_Date		AS LEFT VISUAL	~	AL PIN_TO_PIN	
PSI_Date		NOA_NO		AL RES_LEVEL	
PSI	SAT	NOA_DATE			
PLAN	10%	DATE_INSTALLED	11/1/2001	REMOVAL_DATE	11/5/2010
€€ЭЭ					



SnubbWorks® - Exam Detail	s						
Snul	bber	Location /					
Component No: Serial No:	M20001 14448		Exam Mark		1004 AFW-H-3 IB 253'		
TPNS No: Manufacturer: Model/Type:	Model: PSA-1  Mechanical  PSA-1/M	V	Descrip	tion:	Installed Des		cessible: 🗸
Size: Rated Load:	1 1500	<u> </u>	Cateç Sys Line 1	stem:	DTPG 3  AFW  Safety	Tech	i. <b>Spec.</b> : ☑
				1 253'		Building: Room:	
Drawing Type →	Drawing Name	v		ng Type	Drai	Map No.: wing Name	N/A
<b>€€</b>							X





#### In Review

- Why
  - To ensure Operational Readiness of the Snubber on safety-related systems
  - It is required by the Plant Operating License (Tech Specs or TRM)
  - It is the Law
- Requirements
  - ISTA and ISTD
  - ASME Section XI
- Documentation it isn't complete unless it is documented
  - Checklist for the inspections



We will now take your questions



#### Roles for groups

- Corporation:
- Site:
- Corporate Engineer:
- Site Engineer:
- Planner:
- Performer/Performing org:

• Corporation: TVA

• Site: WBN

- Corporate Engineer: Outage Scope, procedure updates, Outage support, teach pre-outage class for pipefitters.
- Site Engineer: NA
- Planner: Planning including spares, tracking spares, post outage package, scaffold requests
- Performer/Performing org: Removes/Reinstalls, vendors

Corporation: TVA

• Site: SQN


- Corporate Engineer: Outage Scope, procedure updates, Outage support, post outage package, A few signoffs for outage paperwork, teach pre-outage class for pipefitters.
- Site Engineer: NA
- Planner: Planning including Parts for hydraulic rebuilds (no drop/swaps so spares aren't done), scaffold requests
- Performer/Performing org: Removes/Reinstalls, vendors

Corporation: TVA

• Site: BFN

- Corporate Engineer: Outage Scope, procedure updates, Outage support, post outage package, Tons of signoffs for outage paperwork, Determine spares (including TIICS, UNIDS, previous locations), challenge meetings, 7+ actions to verify POs in place (BFN only actions and I am not over them), write WOs for outages,
- Site Engineer: NA
- Planner: Planning including Parts for hydraulic rebuilds, scaffold requests
- Performer/Performing org: Removes/Reinstalls, vendors, teach pre-outage class for pipefitters.

# Lunch Sponsored By




RETURN BY 1:00 PM

# ADMINISTRATIVE ITEMS SCOTT ESPOSITO



- Logistics
- Agenda Overview
  - Conference Planning Committee Report
  - Plant Mod Requirements
  - Train Related Outages
  - Question & Answer Session
  - Afternoon Break
  - Utility representatives only closed session



# Conference Planning Committee Report

# **Committee Members**

- Steve Norman, Chair
- Scott Esposito, Ex-Officio Member
- Mitch Etten-Bohm, Standing Member
- Tim Canter, Standing Member
- Bob Fandetti, Standing Member
- Gus Avila, Standing Member
- John Knezevic (Curtiss-Wright), Summer 2024
- Riley Smith (Curtiss-Wright), Summer 2024
- Grant Nelson (ASC-ES), Summer 2025



## Summer 2025 SNUG

#### Sponsored by:



and



## Summer 2025 SNUG



The DeSoto Hotel Savannah, Georgia July 14, 15 & 16, 2025


Room Rate for Standard Rooms: \$185.00


## Summer 2025 SNUG

The DeSoto Hotel
15 East Liberty Street, Savannah, GA 31401

**Reservations:** (912) 232-9000

Room Rate: \$185.00





# **Hotel Dining**

#### Edgar's Proof & Provision

Edgar's Proof & Provision is an old-fashioned community drinkery offering a selection of 120+ whiskeys, including the private label "Edgar's Truth" bourbon. With indoor and outdoor seating, guests can enjoy a refreshing beverage with Southern comfort food for breakfast, lunch, or dinner. The casual dining menu features locally sourced charcuterie, and favorites such as grilled cheese sandwiches and Southern chicken biscuits served with tomato and jalapeño jam.

#### 1540 Room

Unpretentious and inventive, the 1540 Room delivers a locally sourced culinary experience rich in Savannah traditions. The 1540 Room is one of the only restaurants in Savannah that offers an open-concept show kitchen, sharing the same space as the dining area. Follow the bubbling conversation to the heart of Savannah's historic district and indulge in artistic, Southern-infused cuisine and decadent desserts. Locally sourced with a hands-on focus, 1540 dishes are perfectly paired with cocktails and select wines. The result: an invigorating dining experience that leaves guests satisfied to the core.

#### Buffalo Bayou Coffee

Located in the lobby, Buffalo Bayou Coffee serves local Savannah Coffee Roasters brews alongside gourmet-to-go light fare. Savor the signature Honeybee Latte made with Local Honey with a breakfast sandwich or grab Southern-style fare like Pimento Cheese & Bacon Biscuits and Turkey & Garden Tomato Clubs to go.

# 40<sup>th</sup> Anniversary

The first official conference of SNUG was held in Charlotte, North Carolina during the summer of 1985. SNUG celebrated our 20<sup>th</sup> anniversary with a huge conference in 2005 and invited as many members from the past as we could find. We plan to repeat that by once again inviting as many past SNUG members as we can contact. So, if there is someone at your place of business that was involved with snubbers at one time but has now moved on to other assignments or has retired but you still know how to contact them, please let them know of our plans and also please make sure to send us their contact information.

That being said, when registration opens up for the Summer 2025 SNUG Conference & Trade Show, MAKE YOUR HOTEL RESERVATIONS.

#### DO NOT WAIT!!!

# Future Conference Sponsorship

We begin planning our conferences 18 months in advance, with a goal of having a signed contract 12 months in advance. If your company is interested in sponsoring a future conference, please notify us at least 18 months in advance if possible, so that we can include your organization in the site selection and the planning of conference.

# Future Conference Sponsors

EVENT	UTILITY	VENDOR
Summer 2025	Southern Nuclear	ASC Engineered Solutions
Summer 2026	TBD	Element Materials Technology
Summer 2027	TBD	Lisega
Summer 2028	TBD	Curtiss-Wright
Summer 2029	TBD	ASC Engineered Solutions
Summer 2030	TBD	Element Materials Technology

# Conference Planning Committee Report

# SNUG 2024 Presentation Millstone Handling of Piping and Pipe Support Modifications

**Ed Dundon** 

#### Millstone Units 2 & 3

- Committed to 2012 ASME OM
  - Subsection ISTD 1600 Snubber Modification and Replacement
    - Replacement parts, adjustments, and similar actions that do not change the design (configuration and material) of an item. (ISTA -2000 Definitions)
    - Replacement Snubber: any snubber other than the snubber immediately previously installed at a given location in place. (ISTD -2000 Definitions)
    - Modification alteration in the design of a system, structure or component (ISTA -2000 Definitions).

### Subsection ISTD - 1600 (cont.)

- Snubber replacement activities shall be performed in accordance with Section XI of the ASME Boiler and Pressure Vessel Code, as applicable.
  - Section XI repair/replacement plan
  - 'As Left' Section XI visual inspection VT-3 exam & VT-3 qualified inspector
  - Replacement Snubber or Modified Snubber(s) will shall have proven suitability for application or environment. (Need to follow licensing Code requirements/Construction requirements)

### ISTD - 1620 - Examination & Testing

• Replacement or modified snubbers shall be examined and tested in accordance with written procedures. The applicable requirements of paragraphs ISTD-4100, ISTD-4200, ISTD-5200, and ISTD-5500 shall be included in these procedures. The requirements selected shall ensure that the criteria of paragraphs ISTD-4110, ISTD-4230, and ISTD-5210 can be satisfied.

#### ISTD - 4110 - Preservice Examination

- The initial examination shall, as a minimum, verify the following:
  - (a) **no visible signs of damage or impaired** operational readiness exist as a result of storage, handling, orinstallation.
  - (b) the snubber load rating, location, orientation, position setting, and configuration (e.g., attachments and extensions) are in accordance with design drawings and specifications. Installation records (based on physical examinations) of verification that the snubbers were installed according to the design drawings and specifications shall be acceptable in meeting this requirement.
  - (c) **adequate swing clearance** is provided to allow snubber movement.
  - (d) if applicable, **fluid is at the recommended level**, and **fluid is not leaking from** the snubber system.
  - (e) **structural connections**, such as pins, bearings, studs, fasteners, lock nuts, tabs, wire, and cotter pins, **are installed correctly**.

# Nonmandatory Appendix B Examination Checklist

- Incorrect snubber load rating
- Incorrect installed location
- Incorrect installed orientation (example vented reservoir does not drain out
- Incorrect position setting
- Incorrect snubber configuration
- Inadequate swing clearance
- Snubbers with preset locking screws used for shipment are not removed.
- Protective coverings or shipping plugs not removed

# ISTD - 4230 – Visual Examination Requirements

- **Restrained Movement-** Snubber is capable of restraining pipe movement as designed.
  - Loose fasteners or member corroded or bent (piston rod)
  - Disconnected components
- Thermal Movement- No binding misalignment or deformation is observed.
  - (Hot Check at NOP/NOT)
- Design-Specific Characteristics
  - No design specific defects
  - No snubber fluid issues

#### ISTD - 5210 – Test Parameters

Snubber operational readiness tests shall verify the following:

- Activation is within the specified range of velocity or acceleration in tension and in compression.
- Release rate, when applicable, is within the specified range in tension and in compression. For units specifically required not to displace under continuous load, ability of the snubber to withstand load without displacement.
- Mechanical snubbers, drag force is within specified
- limits, in tension and in compression.

Millstone functionally tests all new snubbers prior to installation independent of vendor test results

#### Historical Mods and Issues at Millstone

- PORV line rerouted for better sloping & new flanged PORV
  - Changes: thermal movements; snubber loads; snubber travel; snubber sizes and snubber orientation
  - Visuals inspections: Initial "as left" cold; Initial as left hot (NOP/NOT); as found cold for 1<sup>st</sup> & 2<sup>nd</sup> refueling after modification (Reference ISTD-4252)
  - Visual inspections thereafter following normal visual inspection for all snubber.
  - Biggest challenge: Management buy- in for the hot visual inspection.

### Historical Mods and Issues (cont.)

- Rerouting of Main Steam line to AFW turbine to stop chattering check valve.
  - Changes: thermal movements; snubber loads; snubber travel; snubber sizes and snubber orientation
  - Visuals inspections: Initial "as left" cold; Initial as left hot (NOP/NOT); as found cold for 1<sup>st</sup> & 2<sup>nd</sup> refueling after modification (Reference ISTD-4252)
  - Biggest challenge: One snubber did not travel to Hot Piston Setting from Computer Analysis
    - Visual examination of near-by pipe supports found a vertical restraint limit horizontal travel of the pipe run. Management buy- in for the hot visual inspection. Changed rigid support to permit horizontal travel will at NOP/NOT.
    - Still snubber travel was limited. Re-analized piping with travel stop. Stresses were within code allows
    - Fall 2024 further investigation for locating the restriction to pipe movement

# ISTD - 4252 — Subsequent Examination Internal

- Subsequent examination internals shall begin at the end of the previous examination interval and conclude at the end of the next refueling
- Interval prior to the completion of the of the second refueling shall not exceed one fuel cycle in duration.
- Interval prior to the completion of the of the second refueling shall be in accordance with Table ISTD-4252-1.

Millstone interpretation of ISTD – 4230 & 4252 for visual examination of snubber modifications:

Initial 'as left' Cold visual examination

Initial 'as left' Hot visual examination

1st Refueling post mod 'as found' Cold visual examination

2<sup>nd</sup> Refueling post mod 'as found' Cold visual examination

Back to normal visual inspection interval for modification snubbers

• Questions?





Snubber Testing During Single Train Outages



#### We are being challenged by our management.

As sites continue to look for more and more ways to reduce the length of refueling outages, one thing that is being considered is to divide the outage into single train outages so that the impact on the outage critical path will be lessened. Our management is continually challenging us to look at our programs and determine if the codes and standards that guide our programs will allow us to get on board and participate. If we tell them that our guiding codes and standards will not permit us to divide our program into single trains and still meet all the requirements, we will be challenged to poll the industry to see what others are doing and to think outside the box and be innovative, while still meeting the code and standard requirements.

The following slides will give you some things to think about when challenged by your superiors.



## Things to consider

- Size of population
  - How many total snubbers are in the population of snubbers to be tested?
- Number of defined test plan groups (DTPGs)
  - How many defined test plan groups (DTPGs) is the population divided into?
- Which test plan is being used?
  - This may be dependent on how many DTPGs you have. If a DTPG contains 370 or more snubbers, you are probably using the 37 plan for that DTPG. If a DTPG has less than 370 snubbers, you are probably using the 10% plan for that DTPG.
- What is the basis of your DTPG makeup?
  - ISTD gives you a lot of flexibility in determining how your population is divided up into DTPGs, but it is not limitless.
     There are some specific guidelines in the code on DTPG makeup.

Let's take a closer look

# Defined Test Plan Groups



defined test plan group (DTPG): a population of snubbers from which samples are selected for testing.



**DTPGs General Requirement.** The DTPGs shall include all snubbers except replacement snubbers and snubbers repaired or adjusted as a result of not meeting the examination acceptance requirements of ISTD-4200. These snubbers shall be exempt for the concurrent test interval.



**DTPG Alternatives.** Except as required by ISTD-5253, the total snubber population may be considered one DTPG, or alternatively, differences in design, application, size, or type may be considered in establishing DTPGs. DTPGs shall not be changed after initiating a test campaign.



Additional DTPG Requirements for Pressurized Water Reactors (PWRs). Snubbers attached to the steam generator and snubbers attached to the reactor coolant pump shall be at least one, separate DTPG.

### Test Plans



**ISTD-5310** The 10% Testing Sample Plan, Sample Size, and Composition **ISTD-5311** Initial Sample Size and Composition. The initial sample shall be 10% of the DTPG, composed according to either (a) or (b).

- (a) As practicable, the sample shall include representation from the DTPG based on the significant features (i.e., the various designs, configurations, operating environments, sizes, and capacities) and based on the ratio of the number of snubbers of each significant feature, to the total number of snubbers in the DTPG. Selection of the representative snubbers shall be random.
- (b) The sample shall be generally representative as specified in (a), but may also be selected from snubbers concurrently scheduled for seal replacement or other similar activity related to service life monitoring. The snubbers shall be tested on a generally rotational basis to coincide with the service life monitoring activity.

### Test Plans



ISTD-5410 The 37 Testing Sample Plan, Sample Size, and Composition

**ISTD-5411 Initial Sample Size and Composition.** An initial sample of 37 snubbers shall be selected randomly from each 37 plan DTPG.

# So, given the parameters we have to work within, the question is:



# Possibly, but it would have to be carefully planned out

If you are using the 37 Plan, the ASME OM code does not provide an allowance for excluding snubbers from potential random selection based on train or division. The 37 Plan requires TOTALLY random selection from each DTPG each cycle, and single train testing would essentially be creating a DTPG for each train, and ISTD-5252 tells us that DTPGs can be divided by "design, application, size or type". There may be room to argue that "application" can include a single train. We are not aware of that argument ever being made, but a site willing make the argument would be breaking new ground.

If you are using the 10% Plan, it might be somewhat easier, but it might also add more snubbers that have to be tested. As discussed above, one possible way to test within a single train is to divide the DTPGs into separate trains by classifying a train as an "application". However, in doing so, the DTPGs that you originally had defined now change sizes, so 10% of the number of snubbers in two (or more) single trains could be more than if you had maintained the snubbers in one DTPG population.

### Other considerations

Limiting testing to a single train could also expose larger vulnerabilities than does random selection from all trains. A big question is a scenario where there is an unacceptable snubber test from a single train on a double train system – where the logical extent of condition question in single train testing would immediately point to the sister snubber on the other train simply due to the initial limitation of the one train sample. In a "normal" 37 Plan sample that is truly random with no train exclusions the randomness of the original sample and the supplemental samples adds a statistical basis to the supplemental testing that is defensible (although one could still argue that the sister snubber should be checked depending on the cause as a FMG, the overall randomness of the initial and supplemental samples meets code basis). In a one train sample where essentially half of the installed snubbers on a system are excluded from consideration the effectiveness of the sampling technique is significantly diluted.


### **Code Case or Relief Request?**

There has been discussion of a code case or relief request to address single train testing, which would include some specific actions to be taken in the opposite train in the event of a failure. But just what those actions would be and how severe they may need to be to satisfy regulators is anyone's guess.

One potential avenue around this would be to utilize OMN-15 to enable skipping an outage – testing every other outage. Then you could define each train as a separate DTPG and test them in alternating outages. Of course, this means meeting the prerequisites first by having a good performance record using "normal" testing, then setting up the Code Case testing for each DTPG. But even then, failures that could affect the other trains or DTPGs may invoke extent of condition actions at any time. You would also not be able to use OMN-13 or code permitted ten-year visual intervals.

### One other thing to consider . . . . . . . .

Trains are typically defined by isolation boundaries such as valves. However, snubbers work within stress problems, which are defined by anchors. So there may be a case where removal of a snubber in one valve defined train may affect the operability of a portion of a different train because of a stress problem boundary that crosses both trains.







Hopefully, this has answered more questions for you than it has created



### **Questions?**





### QUESTION CARDS





# AFTERNOON BEVERAGE BREAK SPONSORED BY



# CLOSED SESSION FOLLOWS. UTILITIES RETURN BY 3:00 PM





## UTILITY ONLY CLOSED SESSION



#### CONFERENCE ADJOURNMENT

SAFE TRAVELS HOME!!